



NOTES:-

- DEMOLITION OF EXISTING TIMBER STRUCTURES TO BE IN ACCORDANCE WITH NBS C20
- EXCAVATION AND BACK FILLING TO BE IN ACCORDANCE WITH NBS D20
- RADON AND METHANE BARRIER AND PIPEWORK TO BE IN ACCORDANCE WITH NBS D21
- EXTERNAL BRICKWORK TO BE IN ACCORDANCE WITH NBS F10
- EXTERNAL WALLING TO BE IN ACCORDANCE WITH NBS F30
- FIRST FIX TIMBER WORK AND STUD WORK TO BE IN ACCORDANCE WITH NBS G20
- FASCIAE BARGEES AND HIGH LEVEL PANELING TO BE IN ACCORDANCE WITH NBS H20
- ROOF COVERING TO BE IN ACCORDANCE WITH NBS H40
- PLASTER BOARDING TO BE IN ACCORDANCE WITH NBS H10
- TOILET CARBICLES AND JPS TO BE IN ACCORDANCE WITH NBS K32
- WINDOWS AND ROOF LIGHTS TO BE IN ACCORDANCE WITH NBS L10
- DOORS TO BE IN ACCORDANCE WITH NBS L20
- FLOOR SCREED TO BE IN ACCORDANCE WITH NBS M10
- PLASTER SKIN TO BE IN ACCORDANCE WITH NBS M20
- CARPETS, BARRIER MATTING AND VINYL TO BE IN ACCORDANCE WITH NBS M50
- DECORATION TO BE IN ACCORDANCE WITH NBS M60
- VANITY UNITS, MIRRORS AND BLINDS TO BE IN ACCORDANCE WITH NBS N10
- WC, U/WB, URINALS, CISTERNS, SINKS, MIRRORS, TOILET ROLL HOLDERS, PAPER TOWEL HOLDERS AND SOAP DISPENSERS TO BE IN ACCORDANCE WITH NBS N13
- FIRE SIGNAGE TO BE IN ACCORDANCE WITH NBS N15
- CAVITY BARRIERS, FLOOR INSULATION, CEILING INSULATION, LOFT HATCH INSULATION AND MINERAL FIBRE INSULATION TO BE IN ACCORDANCE WITH NBS P10
- FIRE STOPPING TO BE IN ACCORDANCE WITH NBS P12
- SHUTTERS AND ARCHITRAVES TO BE IN ACCORDANCE WITH NBS P20
- RAKENONKEY FOR WINDOWS AND DOORS TO BE IN ACCORDANCE WITH NBS P2
- CONCRETE EDGING KURBS TO BE IN ACCORDANCE WITH NBS Q10
- FOOTPATHS AND ACCESS TO DOORS TO BE IN ACCORDANCE WITH NBS Q22
- GRASS AREAS WHERE DEMOLITION HAS TAKEN PLACE AND RENOVATION OF TURF TO SPORTS FIELD TO BE IN ACCORDANCE WITH NBS Q30
- TIMBER FENCING AND METAL FENCING RENOVATION IN ACCORDANCE WITH NBS Q40
- TINDER TREATMENT IN ACCORDANCE WITH NBS Z12
- FIXING AND ADHESIVES IN ACCORDANCE WITH NBS Z20
- CEMENTS AND PORTLANDS IN ACCORDANCE WITH NBS Z21
- SEALANTS IN ACCORDANCE WITH NBS Z22

NO. 1	REMOVAL OF EXTERNAL DOOR SET	DATE	27/01/2021
NO. 2	RENOVATION OF EXTERNAL DOOR SET	DATE	18/01/2021

APPROVED BY: [Signature]

DATE: [Date]

Telford & Wrekin
C O U N C I L

David Siskaway
Head of Property & Design
Dunlop House, PO Box 312, Llewellyn, Telford, Shropshire, TF9 4LB
01779 727274, Telford 5 Star Homes 44(0)1952 384600 / Faxline 44(0)1952 384654
telford@telford.gov.uk, telford@telford.gov.uk, telford@telford.gov.uk

St Georges Primary School
REPLACEMENT CLASSROOMS

DWG TITLE
PROPOSED ELEVATIONS

SCALE	DATE	DESIGN	David B Tomlinson
H:100@A1	DATE	CHK	Bsc (Hons) ABERG IJOB
DATE	DATE	REV	18/01/2021
04.08.11	04.08.11	REV	18/01/2021