


- LEGEND**
- Existing Trees and Hedges to be Retained
Refer to Arboricultural Assessment Report for Land Off Haygate Road, Wellington, by FPCR Environment & Design Ltd
 - Proposed Native Tree in Shrub Planting
Selected Standard trees, 10-12cm girth, 3-3.5m high or large shrub 30-50L to be planted with a single timber stake secured with a rubber tree tie.
 - Proposed Trees in POS
Advanced Nursery Stock, 16-18cm/18-20cm girth, 4.5-6.25m high to be planted with a double timber stake secured with a rubber tree tie.
 - Proposed Ornamental Trees
Heavy Standard, 12-14cm girth, 3.5-4.25m high to be planted with a rubber tree tie.
 - Small Ornamental Tree/Large Shrub
Select Standard trees, 10-12cm girth, 3-3.5m high or large shrub 30-50L to be planted with a single timber stake secured with a rubber tree tie.
 - Proposed Ornamental Shrub Planting
To be planted as 3-5L pots at 3-5 per sq.m. with feature specimen planting in 10-12L pots.
 - Proposed Ornamental Hedge in Front Gardens
Proposed ornamental hedge to be planted as 60cm height 5L pots at 4 per in.m to provide an instant impact.
 - Proposed Native Hedgerow
Proposed native hedge to be 100-125cm height planted in a double row 300mm apart.
 - Grass in Front and Back Gardens
Front and back gardens to be turf.
Grass verges to be turf.
 - Proposed Grass - POS
Grass within POS to be seeded with hard wearing grass.
 - Proposed Bulb Planting in POS
 - Proposed Wildflower Meadow Mix
To be Emorgate EM1 Basic Grassland Mix, supply by Emorgate or similar approved. Including 80% of ornamental grasses and 20% of flowering perennials. Sowing rate 5/gm2.
 - Proposed Pond Edge Mix
To be seeded with Emorgate EP1 Pond Edge Mixture, supply by Emorgate or similar approved. Including 80% of ornamental grasses and 20% of flowering perennials. Sowing rate 5/gm2.
 - Proposed Native Plant Mix
To be whip planting, 60-80cm height at 4 plants per sq.m.
 - Proposed Attenuation Pond
 - Proposed Neutral Grassland
Grassland Mix BSHWFG4 Neutral soils. Sowing rate 5/gm2.
Grass to be left long.

- GENERAL NOTES**
1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
 2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
 3. This drawing is to be read in conjunction with all relevant Architects', Engineers', Specialists, Bills of Quantities and Specifications.
 4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
 5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
 6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
 7. All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
 8. All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

For planting schedule refer to TPM Drawing 2818 - 212



REVISION NOTES

Rev	By	Description	Date
D	KD	Updated in line with comments from LPA	02.02.18
C	KD	Updated in line with architects layout and comments from APT	15.12.17
B	KD	Updated in line with architects layout	08.12.17
A	KD	Updated in line with architects layout	27.11.17

Client
Anwyl Homes/ Bovis Homes

Project
Haygate Road

Description
Planting Plan (Sheet 6 of 12)

Status
For Approval

Scale

Scale #1	Drawn	Checked	Date
1:250	CM	CT	07.08.17
2818	206		D